

RESEARCH ARTICLE

Genome-wide diversity and demographic dynamics of Cameroon goats and their divergence from east African, north African, and Asian conspecifics

Getinet Mekuriaw Tarekgn^{1,2,3*}, Patrick Wouobeng^{3,4}, Kouam Simo Jaures^{3,4}, Raphael Mrode⁵, Zewdu Edea⁶, Bin Liu⁷, Wenguang Zhang⁸, Okeyo Ally Mwai⁵, Tadelle Dessie⁹, Kassahun Tesfaye¹⁰, Erling Strandberg¹, Britt Berglund¹, Collins Mutai³, Sarah Osama¹¹, Asaminew Tassew Wolde², Josephine Birungi³, Appolinaire Djikeng^{3,12}, Félix Meutchieye^{3,4*}

1 Department of Animal Breeding and Genetics, Swedish University of Agricultural Sciences, Uppsala, Sweden, **2** Department of Animal Production and Technology, Bahir Dar University, Bahir Dar, Ethiopia, **3** Biosciences Eastern and Central Africa-International Livestock Research Institute (BecA-ILRI) Hub, Nairobi, Kenya, **4** Faculty of Agronomy and Agriculture, University of Dschang, Dschang, Cameroon, **5** International Livestock Research Institute (ILRI), Nairobi, Kenya, **6** Department of Animal Science, Chungbuk National University, Cheongju, Korea, **7** Nei Mongol BioNew Technology Co.Ltd, Hohhot, China, **8** College of Animal Science, Inner Mongolia Agricultural University, Hohhot, China, **9** International Livestock Research Institute (ILRI), Addis Ababa, Ethiopia, **10** Department of Microbial, Cellular and Molecular Biology, Addis Ababa University, Addis Ababa, Ethiopia, **11** The University of Queensland, Queensland, Australia, **12** Centre for Tropical Livestock Genetics and Health, The University of Edinburgh, Scotland, United Kingdom

* yafetgetinet@gmail.com (GMT); fmeutchieye@gmail.com (FM)

Abstract

Indigenous goats make significant contributions to Cameroon's national and local economy, but little effort has been devoted to identifying the populations. Here, we assessed the genetic diversity and demographic dynamics of Cameroon goat populations using mitochondrial DNA (two populations) and autosomal markers (four populations) generated with the Caprine 50K SNP chip. To infer genetic relationships at continental and global level, genotype data on six goat populations from Ethiopia and one population each from Egypt, Morocco, Iran, and China were included in the analysis. The mtDNA analysis revealed 83 haplotypes, all belonging to haplogroup A, in Cameroon goats. Four haplotypes were shared between goats found in Cameroon, Mozambique, Namibia, Zimbabwe, Kenya, and Ethiopia. Analysis of autosomal SNPs in Cameroon goats revealed the lowest H_O (0.335 ± 0.13) and H_E (0.352 ± 0.15) in the North-west Highland and Central Highland populations, respectively. Overall, the highest H_O (0.401 ± 0.12) and H_E (0.422 ± 0.12) were found for Barki and Iranian goats, respectively. Barki goats had the highest average MAF, while Central Highland Cameroon goats had the lowest. Overall, Cameroon goats demonstrated high F_{IS} . AMOVA revealed that 13.29% of the variation was explained by genetic differences between the six population groups. Low average F_{ST} (0.01) suggests intermixing among Cameroon goats. All measures indicated that Cameroon goats are closer to Moroccan goats than to other goat populations. PCA and STRUCTURE analyses poorly differentiated the Cameroon goats, as did genetic distance, Neighbor-Net network, and neighbor-joining



OPEN ACCESS

Citation: Tarekgn GM, Wouobeng P, Jaures KS, Mrode R, Edea Z, Liu B, et al. (2019) Genome-wide diversity and demographic dynamics of Cameroon goats and their divergence from east African, north African, and Asian conspecifics. PLoS ONE 14(4): e0214843. <https://doi.org/10.1371/journal.pone.0214843>

Editor: Tzen-Yuh Chiang, National Cheng Kung University, TAIWAN

Received: July 30, 2018

Accepted: March 21, 2019

Published: April 19, 2019

Copyright: © 2019 Tarekgn et al. This is an open access article distributed under the terms of the [Creative Commons Attribution License](https://creativecommons.org/licenses/by/4.0/), which permits unrestricted use, distribution, and reproduction in any medium, provided the original author and source are credited.

Data Availability Statement: Mitochondrial DNA sequences of Cameroon goats are deposited in the GenBank (Accession No. MH621412-MH621504). Similarly, genotypic data of all the animals (included in the study) representing 14 goat populations are deposited and available at (<https://datadryad.org/review?doi=doi:10.5061/dryad.mc40jt6>).

Funding: This project was supported by the BecA-ILRI Hub through the Africa Biosciences Challenge

Fund (ABCF) program. The ABCF Program is funded by the Australian Department for Foreign Affairs and Trade (DFAT) through the BecA-CSIRO partnership; the Syngenta Foundation for Sustainable Agriculture (SFSA); the Bill & Melinda Gates Foundation (BMGF); the UK Department for International Development (DFID); and the Swedish International Development Cooperation Agency (Sida). Bin Liu is employed in a private company (Nei Mongol BioNew Technology Co.Ltd). However, the company had no any role in funding any part of the research except paying salary of the author (Bin Liu). The specific role of the author is articulated in the 'author contributions' section.

Competing interests: Nei Mongol BioNew Technology Co.Ltd, Hohhot, 010020, China. This does not alter our adherence to PLOS ONE policies on sharing data and materials.

tree analyses. The haplotype analysis of mtDNA showed the initial dispersion of goats to Cameroon and central Africa from north-east Africa following the Nile Delta. Whereas, the approximate Bayesian computation indicated Cameroon goats were separated from Moroccan goats after 506 generations in later times (~1518 YA), as supported by the phylogenetic net-work and admixture outputs. Overall, indigenous goats in Cameroon show weak phylogenetic structure, suggesting either extensive intermixing.

Introduction

Goats are an important economic resource in Africa. For instance, in Cameroon there are 6.2 million goats [1]. They, together with sheep, provide 21% of the meat demand [2] for 22.8 million people [3]. Their small size, low maintenance requirements, short generation interval, good prolificacy, hardiness, and potential to adapt a wide range of agro-ecological zones have made goats the most important livestock species for many smallholder farmers and pastoral communities [4, 5]. African goats are also known for their heat tolerance (e.g., Egyptian Barki, Sahelian, and Sudanese goat populations) and trypanotolerance (e.g., West African Dwarf) [6–8]. A few goat populations, such as the Nigerian Dwarf goat, a variant of the West African Dwarf, are well-known for their prolificacy. Goats are also important sources of milk and meat and provide financial stability to pastoral communities and smallholder farmers in arid, semi-arid, and mountainous areas of Africa [9–13].

Goats (*Capra aegagrus*) were among the first species to be domesticated, about 10,500 years ago [14–16], and dispersed to various parts of the world [17]. Archaeological data indicate that goats were first introduced to Africa via the Mediterranean Sea coast, Red Sea Hills, and overland via the Sinai Peninsula and Nile Delta around 7000 years ago [18, 19]. The shared haplotypes observed for Ethiopian, Egyptian, and Saudi Arabian indigenous goat populations in a recent mitochondrial DNA (mtDNA) study confirm these routes of dispersion [20].

Modern maternal DNA analysis shows that, of six globally identified mtDNA haplogroups, three (A, B and G) are present in Africa [21, 22]. Haplogroup A has been observed in all regions of the continent, haplogroup B is limited to South Africa and Namibia [22], and haplogroup G has been reported in Egypt [22], Kenya [23], Somalia and Sudan [24, 25], and Ethiopia [20]. However, there is no documented information on the maternal origin of the goat populations in many African countries. Similarly, only a few autosomal marker-based studies have been conducted to characterize the indigenous goats in Africa. In Ethiopia and selected sub-Saharan African countries, studies on the genetic diversity of indigenous goats using microsatellite (SSR) markers have revealed low levels of differentiation among the goat populations [26, 27]. Similarly, studies by Guangul [28] and Tarekegn [29] on the genetic diversity and population structure of two and 14 Ethiopian goat populations, respectively, using 50K SNP chip panel, have both revealed a high level of admixture. High admixture status has also been reported for indigenous goat populations in Morocco and Sudan [30, 31].

In a previous study in Cameroon, eight indigenous goat populations were characterized using SSR markers and, based on the results, these populations were regrouped to four [32], despite the fact that principal component analysis (PCA) in the same study did not show a clear classification pattern. This could be related to lower abundance, in the genome, of the SSR markers used to uncover the structure of the study populations [33]. This suggests that highly abundant, high-resolution markers should be used to unravel the genetic diversity and population structure of indigenous goats in Cameroon, which in turn could help in designing

appropriate breeding strategies. Therefore, the aim of this study was to describe the genetic diversity and demographic dynamics of Cameroon goat populations using mitochondrial DNA and genome-wide autosomal markers.

Materials and methods

Sampling for this work was conducted in close collaboration with the Directorate of Veterinary Services under the supervision of the Ministry of Livestock in Cameroon. No animal sacrifice was required; hair samples were collected from 388 animals owned by smallholder farmers in rural areas of Cameroon (S1 Table).

Sampling, DNA extraction, PCR amplification and sequencing

Genomic DNA was extracted from four indigenous goat populations in Cameroon (Central Highland, North-west Highland, Forest, Djallonke) using the Qiagen DNA extraction protocol and DNeasy® Blood & Tissue Kit (http://diagnostics1.com/MANUAL/General_Qiagen.pdf). Samples from the Djallonke (n = 48) and North-west Highland (n = 45) goat populations were used for mtDNA analysis. The PCR amplification steps, PCR reaction concentrations, and PCR programs, including the sequencing technology, were carried out as described in Tarekgn et al. [20]. For analysis of autosomal marker-based variation, 324 animals representing all four populations of Cameroon indigenous goats (Central Highland: n = 94; North-west Highland: n = 166; Forest goat: n = 31, and Djallonke: n = 33) were genotyped using the Caprine 50K SNP chip panel [34]. For comparison, we included genotype data from six Ethiopian indigenous goat populations (Ambo: n = 119; Afar: n = 49; Keffa: n = 51; Gumez: n = 42; Long-eared Somali: n = 48; Nubian: n = 47), representing East Africa; Egyptian Barki goat (n = 52) and Moroccan goat (n = 30), representing north Africa; one population from Iran (n = 9), and Cashmere goat (n = 108) from China. In total, 848 animals were included in the analysis. The inclusion of Ethiopian goats took into account two main agro-climates. The Gumez and Keffa populations are found in the humid environment of north-west and southern Ethiopia, while the Nubian, Afar, and Long-eared Somali goats derive from the dry and arid environments of north, north-east, and south-east regions of Ethiopia. The Keffa and Gumez populations were also used to test the hypothesis that the genotypes of goat populations found in the north, west, and south of Ethiopia are influenced by West African Dwarf and Central African Dwarf goat genotypes [35]. Furthermore, the north and east regions of Ethiopia were assumed to be the initial entry points of goats into the country [20, 29].

Data analysis

The *d-loop* sequence. All chromatograms were visualized using CLC Workbench 7.0.4 (CLC Bio-Qiagen). The sequence fragments were edited manually using MEGA6 [36] to correct possible base calling errors. Multiple sequence alignments were performed in CLC Workbench with the ClustalW algorithm [37] and variable sites were scored against the *C. hircus* reference sequence (GenBank accession number: GU223571: direct submission). In total, we generated 93 sequences and determined the number of haplotypes with DnaSP v5 10.01 [38]. The level of genetic diversity represented by the number of haplotypes, haplotype diversity (H_d), nucleotide diversity (π), and mean number of nucleotide differences between haplotypes and their standard deviations were determined for each goat population and across all populations, using ARLEQUINv3.5.2 [39].

To visualize the genetic relationship between individuals and populations, a phylogenetic tree was constructed using all the haplotypes with the Neighbor-Joining (NJ) algorithm implemented in MEGA6. The level of confidence associated with each bifurcation was evaluated

with 1000 bootstrap replications. To complement the NJ tree, obtain further insights into the genetic relationships between the haplotypes, and determine the number of distinct mtDNA *d*-loop haplogroups present in the dataset, the median-joining (MJ) network [40] was constructed using Network v4.6 (www.fluxus-engineering.com). All mutations and character states were equally weighted. To visualize the variation and the gene flow in Cameroon goats in the context of the global caprine variation, 570 sequences from 29 countries representing the six globally defined mtDNA *d*-loop haplogroups [22] were retrieved from GenBank (S2 Table). The reference sequences for each haplogroup were incorporated into the NJ phylogenetic and MJ network analysis. These analyses were limited to the 481 bp of the first hypervariable (HVI) region of the mtDNA *d*-loop [21], which corresponded to positions 15709–16190 bp of the *C. hircus* mitochondrial reference sequence (GenBank accession number: GU295658).

Population demographic history and dynamics were inferred from haplotype mismatch distribution patterns [41] for each population and the haplogroups revealed by the MJ network analysis. Departures of the observed sum of squares differences (SSD) from the simulated model of demographic or spatial expansion were tested with the Chi-square test of goodness of fit statistic and Harpending's raggedness index "*r*" [42], following 1000 coalescent simulations. Analysis of mismatched distribution patterns was performed with two coalescent-based estimators of neutrality, Fu's F_S [43] and Tajima's D [44]. The significance of these two statistics was tested with 1000 coalescent simulations implemented in ARLEQUIN v3.5.2.

Single nucleotide polymorphism (SNP) genotypes. All the four Cameroon goat populations analyzed and the 10 reference populations were genotyped using the caprine 50K SNP BeadChip array (Illumina Inc., San Diego, CA) [34]. Autosomal SNPs were filtered for call rate by sample and marker $\geq 90\%$ and minor allele frequency (MAF) $\geq 5\%$. After applying these quality control criteria, 43421 SNPs for 848 animals remained for analysis. To avoid the effects of ascertainment bias on the level of admixture, these 43421 SNPs were subjected to linkage disequilibrium (LD) pruning, leaving 7930 SNPs for population structure analysis. However, based on the above filtering criteria Forest goat population showed that 95.41% of the markers for this population were monomorphic loci, and therefore we excluded this population from further downstream analysis.

Statistical analysis

Genetic diversity and differentiation. Within-breed genetic diversity, represented as observed heterozygosity (H_O), expected heterozygosity (H_E), inbreeding coefficient (F_{IS}), and deviation from Hardy-Weinberg equilibrium (HWE), was determined with ARLEQUIN v3.5.2. Analysis of molecular variance (AMOVA) was performed using the same software to apportion genetic variance within and between populations and among groups. The goat populations were considered as a group based on their country of origin. The distribution of MAF was assessed based on the following categories: fixed alleles (MAF = 0.00), rare alleles ($0 < \text{MAF} < 0.05$), intermediate alleles ($0.05 \leq \text{MAF} < 0.10$), common alleles ($0.10 \leq \text{MAF} \leq 0.5$), and polymorphic SNPs (MAF > 0.01).

Genetic relationships and population structure. Population pairwise genetic differentiations (F_{ST}) [45] and Reynolds' genetic distances [46] were estimated with ARLEQUIN v3.5.2. A Neighbor-Net network and NJ phylogenetic tree were constructed using the pairwise genetic distances with SplitsTree ver.4.10 [47] and TASSEL [48], respectively. To further investigate genetic relationships, we carried out PCA using allele frequency data with the SNPRelate R package [49, 50]. The population genetic structure based on SNP information was evaluated using STRUCTURE v.2.3.4 [51] assuming hypothetical population clusters (K) ranging

between 2 and 15. For each K -value, we carried out five runs of 20,000 Markov chain Monte Carlo iterations after a burn-in of 10,000 iterations. The STRUCTURE output was further analyzed in STRUCTURE HARVESTER [52] and the ΔK method [53] was used to determine the optimal number of genetic groups present in the dataset.

Approximate Bayesian Computation (ABC) simulations. To infer the population history of Cameroon goat populations, we analysed HVI d -loop region of mtDNA and autosomal SNP markers using Approximate Bayesian Computation (ABC) simulations [54] implemented in DIYABC Ver. 2.1.1.0 [55]. Both data sets were analysed separately. For mtDNA ABC analysis, a total of 627 HVI region of mtDNA sequences were used and these sequences were grouped based on geographical regions as follows. 1) Cameroon goats; 2) East African goats (Ethiopia and Kenya); 3) North Africa (Morocco, Algeria, Tunisia, Libya and Egypt); 4) Southern Africa (Mozambique, Namibia and Zimbabwe); 5) Middle East and southern Asia (Iran, Iraq, Saudi Arabia and Pakistan). The number of sequences from each country is present at S2 Table. Four demographic scenarios were tested (Fig 1A) assuming that Cameroon goat populations were descended from: east Africa (scenario 1); north Africa (scenario 2); southern Africa (scenario 3); east Africa and north Africa simultaneously (scenario 4). Whereas, for autosomal SNP markers, 1500 SNPs from 848 animals were randomly picked from the 43421 SNPs that qualified the quality control criteria, and used for the ABC evaluation. Three demographic scenarios were tested as indicated in the figure (Fig 1B).

The reference tables were built by 100,000 and one million pods (pseudo-observed data sets) per scenario per set of priors for the autosomal markers and mtDNA, respectively using the default mutation settings. We compared the scenarios by estimating posterior probabilities with the logistic regression method using 0.1% (for mtDNA sequence) and 0.01% (for autosomal SNP markers) of the simulated datasets [56]. For the best model, posterior distributions of the parameters were estimated with a logit-transformed linear regression on the 0.1% (for mtDNA sequence) and 0.01% (for autosomal SNP markers) simulated datasets closest to the observed data [55, 57].

Results

The mtDNA d -loop sequence variation and genetic diversity

In all, 93 sequences of the mtDNA d -loop region were obtained. These sequences were deposited in GenBank (Accession No. MH621412-MH621504). From 1211 bp of the d -loop that was aligned against the caprine reference sequence (Accession No. GU223571; direct submission), 78 variable sites were detected and these defined 83 haplotypes (Table 1). The first haplotype (H1) was shared by the two Cameroon populations analyzed (Djallonke, North-west Highland), whereas H11 was shared by goat populations from Cameroon, Mozambique, Namibia, and Zimbabwe (S3 Table). Similarly, haplotypes H10 and H32 were shared by Cameroon and Ethiopian goats, while haplotype H16 was shared by Cameroon and Kenyan goats. The Cameroon goats did not share any haplotype with goats from west and north Africa, or from outside Africa. The two Cameroon goat populations showed high levels of genetic diversity (average haplotype diversity 0.996 ± 0.006 for Djallonke and 0.993 ± 0.006 for North-west Highland). Average nucleotide diversity was higher for Djallonke goats ($\pi = 0.00895 \pm 0.00050$) than for North-west Highland goats ($\pi = 0.00697 \pm 0.00058$).

Phylogenetic analysis based on mtDNA. The NJ tree constructed for Cameroon goats revealed one well-resolved cluster of haplotypes (Fig 2). The MJ network incorporating 570 reference sequences revealed this cluster to be haplogroup A (Fig 3).

Population and historical demographic dynamics. Mismatch distribution patterns were used to assess the demographic dynamics of the haplogroup revealed by the NJ tree and MJ




Fig 1. Regional representation of goat populations to infer the historical gene flow towards Cameroon examined using Approximate Bayesian Computation implemented in DIYABC. a) Based on mtDNA, Cameroon goats were descended either from east Africa (scenario 1), north Africa (scenario 2), southern Africa (scenario 3) or east and north Africa (scenario 4). b) Based on autosomal SNP markers, Cameroon goats were descended either from east Africa (Ethiopia; scenario 1), north Africa (Morocco; scenario 2) or east (Ethiopia) and north (Morocco) Africa (scenario 3).

<https://doi.org/10.1371/journal.pone.0214843.g001>

network (Fig 4). For each population, the mismatch distribution patterns were unimodal and the observed pattern of mismatches did not deviate significantly from that expected in either a spatial or demographic expansion model (Table 2). Similar results, indicating a unimodal pattern of mismatch distribution with the observed pattern that did not deviate significantly from the expected pattern, were observed for haplogroup A, which included all Cameroon goats (Fig 3; Table 2). Negative values were obtained for Fu’s F_S and Tajima’s D , but the latter was not significant ($P = 0.14200$). These results provide evidence of spatial and/or demographic expansion by Cameroon goats.

SNP genotype analysis

Intra-population genetic variability. The proportion of polymorphic SNPs ranged from 95% (North-west Highland) to 99.7% (Barki) (Table 3). The proportion of SNPs deviating significantly from HWE ($P < 0.05$) ranged from 1.70% (Iranian goat) to 17.33% (North-west Highland goats). The overall mean value of H_O was 0.370 ± 0.140 (range 0.335 ± 0.13 (North-west Highland) to 0.401 ± 0.12 (Barki goat)). The overall mean value of H_E was 0.383 ± 0.127 (range 0.352 ± 0.15 (Central Highland) to 0.422 ± 0.12 (Iranian goats)). The average inbreeding coefficient, F_{IS} , was lowest (-0.02) for Chinese Cashmere goats and highest (0.08) for North-west Highland Cameroon goats. The Cameroon goats had an average F_{IS} value of 0.05.

The overall mean MAF was 0.288, and the lowest (0.258) and highest (0.320) values were observed in Central Highland and Barki goats, respectively. Comparatively low estimates of MAF were obtained for Cameroon goats, which was in agreement with the low estimates of heterozygosity. The distribution of MAF showed that percentage of fixed SNPs (MAF = 0.00) ranged from 0.00% in Barki to 4.07% in Djallonke, with an overall mean of 1.62% across

Table 1. Genetic diversity of indigenous Djallonke and North-west Highland goats in Cameroon, as revealed by mitochondrial DNA (mtDNA) analysis.

Population	N	S	H	Hd ± SD	$\pi \pm SD$	K
North-west Highland	48	58	42	0.993±0.006	0.00697±0.00058	8.425
Djallonke	45	63	41	0.996±0.006	0.00895±0.00050	10.807
All sequences	93	78	83	0.995±0.002	0.00805±0.00039	9.730

N = number of samples; S = number of segregating sites; H = number of haplotypes detected; Hd = haplotype diversity; SD = standard deviation; π = nucleotide diversity; K = average number of nucleotide differences.

<https://doi.org/10.1371/journal.pone.0214843.t001>




Fig 2. Neighbor-joining (NJ) tree for the Cameroonian goat populations studied.

<https://doi.org/10.1371/journal.pone.0214843.g002>

populations (Fig 5; S4 Table). Rare alleles ($0 < \text{MAF} < 0.05$) were not observed in Iranian goats. Highly polymorphic SNPs ($\text{MAF} \geq 0.30$) accounted for 51.14% of the total number of SNPs (range 43.33% for Central Highland to 60.45% for Moroccan goats). The overall mean value of the common alleles ($0.10 \geq \text{MAF} \leq 0.5$) was 88.28% (range 80.79% for Central Highland to 95.41% for Moroccan goat), while the overall mean of polymorphic SNPs ($\text{MAF} > 0.01$) was 97.85%.

Population genetic differentiation and structure

The AMOVA results for the 13 populations grouped by country of origin (Cameroon, Ethiopia, Egypt, Morocco, Iran, and China) revealed that 13.29% ($P < 0.0001$) of the total genetic variation was explained by genetic differences between groups and 81.67% of the variation occurred within individuals (Table 4). Separate analysis of Cameroon goats showed that 1.11%




Fig 3. Median-joining (MJ) network graph of Cameroon goat populations and of reference haplotypes from different countries.

<https://doi.org/10.1371/journal.pone.0214843.g003>




Fig 4. Demographic dynamics revealed by mismatch distribution analysis for haplogroup A goats and for indigenous Djallonke and North-west Highland goat populations in Cameroon.

<https://doi.org/10.1371/journal.pone.0214843.g004>

of the variation could be attributed to genetic differences between the three populations included in the analysis (Djallonke, North-west Highland, Central Highland) (S5 Table).

Among the Cameroon goats, the overall average F_{ST} value was 0.012. This value is lower than the average F_{ST} value of Ethiopian goats (0.032) included in this study. The pair-wise F_{ST} genetic distance ranged between 0.008 (Djallonke, North-west Highland) and 0.253 (Barki, Central Highland) (S6 Table). Barki goat proved to be the most differentiated from the other study populations ($F_{ST} = 0.176-0.253$). Both F_{ST} and Reynolds' genetic distances showed that Ethiopian goats were more differentiated from Barki goats than from Cashmere and Iranian goats. Cameroon goats were more differentiated from Barki and Cashmere goats than from Iranian goats.

Phylogenetic and population structure analyses. The Neighbor-Net network showed that Cameroon goats were highly differentiated from the other goat populations, but were relatively close to Moroccan goats (Fig 6). Compared with Ethiopian goats, very few internal nodes were observed among Cameroon goats and the latter goat populations arose after few population subdivisions. The Neighbor-Net network and NJ phylogenetic trees differentiated the goat populations by country of origin (Cameroon, Ethiopia, Egypt, Morocco, Iran and China). However, there was weak differentiation among the Cameroon goats (Figs 6 and 7). Iranian and Cashmere goats were positioned between Ethiopian and Barki goats. The Neighbor-Net network showed that the three populations (Iranian goat, Cashmere, and Barki) arose from the same clade (Fig 7).

In the PCA, principal components PC1 and PC2 accounted for 38.64% and 22.53% of the total variation, respectively (Fig 8A). PCA separated the study populations according to their country of origin, agreeing with the results of the Neighbor-Net network and NJ phylogenetic trees (Figs 6 and 7). In plots of PC1 and PC2, and PC1 and PC3 (Fig 8B), the Moroccan goat was closer to Cameroon goats than to other populations. As also revealed by the NJ tree, Barki and Cashmere goats were distantly clustered from the other populations and the three Cameroon goat populations were poorly differentiated from each other by both PC1 and PC2, and PC1 and PC3.

Table 2. Results of neutrality test analysis on indigenous Djallonke and North-west Highland goat populations in Cameroon.

Population	N	S	SSD (p-value)	Raggedness index "r" (p-value)	Tajima's D (p-value)	Fu's F_S (p-value)
North-west Highland	48	58	0.00172 (0.46000)	0.00786 (0.53000)	-1.23868 (0.10000)	-24.82673 (0.00000)
Djallonke	45	63	0.00276 (0.66000)	0.00463 (0.91000)	-0.88535 (0.18400)	-24.56169 (0.00000)
All	93	78	0.00224 (0.56000)	0.00624 (0.72000)	-1.06201 (0.14200)	-24.69421 (0.00000)

N = sample sizes; S = segregating sites; SSD = sum of squared deviations

<https://doi.org/10.1371/journal.pone.0214843.t002>

Table 3. Single nucleotide polymorphisms and within-population genetic diversity in the study goat populations.

Population	N	H_O	H_E	F_{IS}	MAF	Mon (%)	Poly (%)	HWE (%) ($P < 0.05$)
Djallonke	33	0.348±0.15	0.366±0.14	0.05	0.265	1867(4)	41558(96)	1753 (4.0)
CH	94	0.341±0.15	0.352±0.15	0.03	0.258	1799(4)	41626(96)	2371 (5.5)
NWH	166	0.335±0.13	0.363±0.14	0.08	0.275	2211(5)	41214(95)	7525 (17.3)
Gumez	42	0.376±0.14	0.380±0.13	0.01	0.285	893(2)	42532(98)	1579 (3.6)
Keffa	51	0.353±0.14	0.374±0.13	0.06	0.279	1116(3)	42309(97)	2565 (5.9)
Ambo	119	0.371±0.13	0.379±0.13	0.02	0.289	873(2)	42522(98)	2845 (6.6)
LES	48	0.378±0.14	0.382±0.13	0.01	0.288	668(1)	42757(99)	1581 (3.6)
Afar	49	0.383±0.13	0.391±0.12	0.02	0.299	402(1)	43023(99)	1652 (3.8)
Nubian	47	0.366±0.13	0.395±0.12	0.07	0.303	491(1)	42934(99)	2942 (6.8)
Iranian goat	9	0.392±0.18	0.422±0.12	0.08	0.305	1035(2)	42390(98)	740 (1.7)
Cashmere	108	0.369±0.15	0.363±0.14	-0.02	0.271	1286(3)	42139(97)	1781 (4.0)
Barki	52	0.401±0.12	0.410±0.11	0.02	0.320	129(0.3)	43296(99.7)	1743 (4.0)
Moroc.	30	0.388±0.13	0.411±0.11	0.06	0.317	149(0.3)	43276(99.7)	1591 (3.7)

N = no. of samples, NWCH = North-west Highland; CH = Central Highland; Moroc = Moroccan goat; LES = Long-eared Somali; H_O = observed heterozygosity, H_E = expected heterozygosity, F_{IS} = inbreeding coefficient, MAF = minor allele frequency, Mono = monomorphic loci; Ply = polymorphic loci; HWE = deviation from Hardy-Weinberg equilibrium.

<https://doi.org/10.1371/journal.pone.0214843.t003>

The results of the STRUCTURE analysis ($2 \leq K \leq 15$) are present in Fig 9. In the dataset used, $K = 6$ was the optimal K value (S1 Fig) and Cameroon goats demonstrated two major genetic backgrounds. In the first genetic background (at cluster2), Central Highland, North-west Highland, and Djallonke goats had 53.66%, 91.60%, and 63.72% similar genetic background, respectively, in which Moroccan goat shared 16.31% (S7 Table). North-west Highland (43.06%) and Djallonke (34.26%) goats shared the next highest proportion of common genetic background at cluster4, in which Moroccan goat shared 26.26% similar genetic background. Similarly, the goat populations found in hot and arid areas of Ethiopia (Afar, Long-eared Somali, and Nubian) separated from the cohorts found in highland and humid environments




Fig 5. Distribution of minor alleles across 13 goat populations, obtained using 43421 autosomal single nucleotide polymorphism (SNP) markers. MAF = minor allele frequency.

<https://doi.org/10.1371/journal.pone.0214843.g005>

Table 4. Analysis of molecular variance (AMOVA) results for 13 goat populations in six population groups (Cameroon, Ethiopian, Cashmere, Moroccan, Egyptian, Iranian).

Source of variation	Degrees of freedom	Sum of squares	Variance component	Percentage of variation
Among groups	5	1617817.146	1256.26969	13.29
Among populations within groups	7	235892.839	197.88555	2.09
Among individuals within populations	835	6912260.984	278.89152	2.95
Within individuals	848	6546877	7720.37382	81.67
Total	1695	15312847.97	9453.42058	

Fixation indices: $F_{IS} = 0.035$; $F_{SC} = 0.024$; $F_{CT} = 0.133$; $F_{IT} = 0.183$; $P < 0.00000$ for all indices

<https://doi.org/10.1371/journal.pone.0214843.t004>

(Ambo, Keffa, and Gumez) at $K = 6$. Ethiopian (Afar, Long-eared Somali, and Nubian), Iranian, and Moroccan goats shared 45.43% to 76.16% similar genetic background at cluster5. This is in line with the results of NJ phylogenetic tree and Neighbor-Net network. However, there was only a very small proportion of common genetic background (6.4–10.8%) between Ethiopian and Cameroon goat populations.

The Bayesian modelling implemented in DIYABC indicated that scenario 2 (Fig 2) was the best fitted model in logistic regression (posterior probability > 0.9126 for mtDNA; > 0.7959 for autosomal SNP markers) (Fig 10; S8 Table) indicating that the southward dispersion of goats from north Africa more explains than the dispersion route from east and southern Africa towards Cameroon. Based on the estimation of posterior distribution for the autosomal SNP markers, the median values of the divergence time showed that the Cameroon goats isolated for the last 506 generations (5% quantile (q_{050}) = 35.9 generations–95% quantile (q_{950}) = 2440 generations) from Moroccan goats (Table 5) which is approximately 1518 years ago assuming three years generation interval per generation.

Discussion

The *d-loop* sequence analysis

In this study, we analyzed mtDNA *d-loop* sequences of two Cameroon indigenous goat populations (Djallonke and North-west Highland) to assess their maternal origin and historical demography. We observed 83 haplotypes defined by 78 variable sites. In Nigeria, 68 haplotypes




Fig 6. Neighbor-Net network analysis of the 13 goat populations analyzed, based on pair-wise (F_{ST}) genetic distances using 43421 autosomal single nucleotide polymorphisms (SNPs).

<https://doi.org/10.1371/journal.pone.0214843.g006>




Fig 7. Neighbor-joining (NJ) phylogenetic tree derived from 43421 autosomal single nucleotide polymorphisms (SNPs) of the 13 goat populations analyzed.

<https://doi.org/10.1371/journal.pone.0214843.g007>

generated from 68 polymorphic sites have been reported from 110 sequences in three goat populations (two Nigerian goat populations and one South African Kalahari Red goat population) [58]. In Democratic Republic of Congo (DRC), 56 haplotypes defined from 124 polymorphic sites of 111 animals of three indigenous goat populations have been detected [59]. In east Africa, 29 haplotypes have been identified in 60 sequences of Kenyan indigenous goats and 231 haplotypes have been defined by 174 polymorphic sites from analysis of 309 individuals from 13 Ethiopian goat populations [20, 23]. In north Africa, 40 haplotypes defined from 64 polymorphic sites have been observed in 44 individuals of three Moroccan goat populations [60]. The difference in number of haplotypes detected in these studies could be related to differences in number of populations and sample size employed, variations in the size of the amplified region in mtDNA, and narrowness/wideness of the gene pool in the countries studied. In the present study, we observed 33 median vectors in the MJ network (data not shown). These median vectors could represent unsampled haplotypes or haplotypes that were introduced into the study region but became extinct either upon arrival or afterwards [20]. The relatively low number of median vectors observed could also be because of the presence of a single haplogroup (haplogroup A) arriving in the region.

To evaluate the genetic relationships between the 83 Cameroon goat haplotypes, we constructed an NJ tree and MJ network. The clustering pattern of the haplotypes revealed one well-resolved haplogroup lacking a phylogeographic structure (Figs 2 and 3). Further analysis incorporating reference haplotypes revealed it to be haplogroup A. This haplogroup has previously been reported in Nigeria [22, 58] and Senegal [22, 24]. In contrast, Okpeku et al. [61] suggested the presence of multiple maternal origins of goats in Nigeria following the high degree of genetic admixture observed. However, the results of MJ network and mismatch distribution analyses obtained in that study did not implicitly support the suggested multiple origin, but rather a haplogroup.

To provide insights into the route of dispersal of goats towards Cameroon, we included an additional 570 HVI sequences from 29 countries downloaded from GenBank (S3 Table) and




Fig 8. Principal component (PC) analysis plots for the 13 goat populations studied, based on 43421 autosomal single nucleotide polymorphisms (SNPs): a) PC1 and PC-2; b) PC1 and PC3.

<https://doi.org/10.1371/journal.pone.0214843.g008>

182 unpublished sequences generated from goats in DRC and Sudan in our analysis. The results showed that Cameroon goats share haplotypes with goats from southern Africa (Mozambique, Namibia, Zimbabwe), east African (Sudan, Ethiopia, Kenya), and DRC. Similarly, the goat populations in Kenya, Ethiopia, Sudan, and DRC share 22 haplotypes. These findings indicate that the initial gene flow or route of dispersion could be from Egypt following the Nile Delta to Sudan and Ethiopia, and then to Cameroon. Based on the archaeological evidence, goats arrived in north Africa from the Fertile Crescent in 5000 BC [18] and are believed to have dispersed southwards following the Nile valley into Sudan and Ethiopia [62]. On the other hand, the southward dispersion of the livestock species from Sahara and Maghreb regions around 2000 BC was restricted by tsetse infestation [63–65]. This dispersion was limited to the Nile Valley route to the south and a tsetse-free corridor to the east along the foothills of the Ethiopian highlands [66, 67]. In studies using modern DNA, the shared haplotypes (all from haplogroup A) detected in Ethiopian and Egyptian goats [20] support the archaeological evidence. The dispersion of goats among Cameroon, east Africa, and southern Africa countries




Fig 9. Genetic structure of the 13 study populations evaluated using STRUCTURE.

<https://doi.org/10.1371/journal.pone.0214843.g009>

(as supported by the shared haplotypes among goats from Cameroon and eastern and southern Africa countries) could be associated with the movement of the Bantu speaking population. The linguistic and archaeological inferences indicate that the Bantu speaking population started moving to the Great Lake (east) and then to southern Africa [68–70] from eastern Nigeria and west Cameroon [71–74] around 3000–5000 years ago [75–78]. Recent SSR and genome-wide high density SNP chip array-based analyses have also revealed a similar dispersion route of the Bantu speaking population [79, 80]. In goats, it has been postulated that the West African Dwarf goat family could have influenced the genetic composition of east African goats, particularly those found in north-west, west, and south-west parts of Ethiopia [35]. This could possibly be linked to movement of the Bantu speaking population.

In the present study, no shared haplotype was observed between Cameroon and north and west African goats, despite expected gene transfer from north Africa via the Niger valley and Atlantic coastline to Cameroon [19]. This could possibly be due to the few number of reference




Fig 10. Logistic regression analysis the scenarios inferred using DIY ABC: a) mtDNA; b) autosomal SNP markers.

<https://doi.org/10.1371/journal.pone.0214843.g010>

Table 5. Original parameter estimation and statistics (Mean, median, mode and quantiles) of the posterior distribution for the scenarios (in autosomal SNP markers) with the highest posterior probabilities.

Parameter	Mean	Median	Mode	q050	q250	q750	q950
N1	8.01e+03	8.56e+03	9.48e+03	4.32e+03	7.24e+03	9.35e+03	9.85e+03
N2	6.64e+03	7.02e+03	9.05e+03	2.13e+03	5.11e+03	8.59e+03	9.73e+03
N3	2.99e+03	2.16e+03	2.16e+02	1.25e+02	7.32e+02	4.73e+03	8.53e+03
N4	3.02e+02	1.74e+02	5.35e+01	2.51e+01	7.84e+01	3.58e+02	8.53e+02
N5	1.87e+03	1.01e+03	1.35e+02	7.69e+01	3.89e+02	2.56e+03	7.12e+03
N6	1.38e+02	9.79e+01	1.00e+01	1.55e+01	4.71e+01	1.81e+02	3.88e+02
t1	7.94e+02	5.06e+02	2.08e+01	3.59e+01	1.90e+02	1.11e+03	2.44e+03
t2	2.26e+03	1.94e+03	8.33e+02	3.97e+02	1.07e+03	3.20e+03	5.16e+03
t3	4.89e+03	5.04e+03	5.17e+03	1.88e+03	3.58e+03	6.24e+03	7.64e+03
t4	5.93e+03	6.01e+03	5.81e+03	2.89e+03	4.75e+03	7.23e+03	8.66e+03
t5	6.50e+03	6.54e+03	6.50e+03	3.32e+03	5.29e+03	7.88e+03	9.16e+03
td	8.13e+03	8.55e+03	9.95e+03	4.85e+03	7.18e+03	9.44e+03	9.92e+03
NA	2.95e+03	2.17e+03	2.61e+02	1.51e+02	8.94e+02	4.62e+03	8.24e+03

N1-N2-N3-N4-N5-N6 = Cameroon-Ethiopian-Moroccan-Barki-Iranian-Cashmere goat populations effective population sizes; NA = effective population size of the starting population; t1 = time of divergence of Cameroon goats from Moroccan goats in generations (3 years per generation in goats); td = divergence time from the starting population.

<https://doi.org/10.1371/journal.pone.0214843.t005>

sequences from north and west Africa used in this study (S2 Table). Results of the population admixture and the approximate Bayesian computation (ABC) better explained the gene flow from north Africa to Cameroon and west Africa in later times (described in later section).

Our mismatch distribution analysis revealed a unimodal pattern for each population and haplogroup A. A similar demographic pattern has been observed in Nigerian goats [58, 61], but not in Ethiopian [20] and Somalian indigenous goats [24], which show a bimodal pattern. This suggests differences in demographic history between goat populations found in Cameroon and west Africa and those from east Africa. It also suggests a single major expansion event of goats into central (Cameroon) and west Africa regions.

The SNP chip analysis

In the present study, the results for the Forest goat population from Cameroon showed that most (95.41%) of the markers for this population was monomorphic loci. This could be explained by small population size, limited gene flow to the forest environment, and/or the tsetse fly challenge for immigrant animals. The other possible reason could also be ascertainment bias [81], such that the SNP chip array may not be able to appropriately serve for goats found in the forest environment. A similar finding (99.6% monomorphic loci) has been reported for Swiss Ibex [81]. The accumulation of monomorphic loci observed for the Forest goat population in our study has an implication on survival of the population and appeals a need to design and implement conservation and breeding strategies to protect the population from the risk of extinction. However, whole-genome scanning may provide a fuller picture of the status of the population.

Intra-population genetic variability. A low overall mean value of fixed SNPs (1.62%) was observed in this study (Fig 5; S4 Table). The overall average value of rare alleles ($0.01 \leq \text{MAF} \leq 0.05$) (4.26% of 43421 SNPs) was higher than in Italian goats (0.46% of 51136 SNPs) [82]. Cashmere and Cameroon goats had the highest percentages of rare variants. This could be because of balancing selection [83–84], whereby Cameroon goats could be naturally selected

to adapt to the humid environment and Cashmere goat is a specialized breed, artificially selected for successive generations for production of cashmere fiber. Low estimates of rare alleles were recently reported in Sudanese goats (1.8% for Desert goat and 3.1% for Taggar) [31]. In the present study, we observed a relatively low level of genetic diversity in Cameroon goats, while Barki, Moroccan, and Iranian goats had the highest heterozygosity estimates (Table 3). The lack of heterozygosity in the three Cameroon goat populations analyzed could be because of the high level of inbreeding, as also indicated by the high proportion of SNPs deviating from HWE ($P \leq 0.05$) (Table 3), or because of sampling bias, small flock size, and poor breeding and flock management strategies.

Population genetic differentiation and structure. Based on AMOVA, the genetic variation (13.29%) observed among the goat populations in Cameroon, Ethiopia, Egypt, Morocco, Iran, and China (Table 4) is similar to the variation (11.86%) reported for Angora goats in South Africa, France, and Argentina genotyped with 50K SNP chip array [85]. In a separate analysis of Cameroon goats, we observed 1.11% variation between the populations (S5 Table). This is much lower than the variation reported for Sudanese goats (6.96%) [31] and Italian goats (7.49%) [82]. The low genetic differentiation we observed between Cameroon goat populations could be attributed by intermixing of animals between households and villages and across geographical regions (S6 Table), suggesting to in place animal regulatory strategy. On the other hand, most of the variation is explained by within population variation that could be contributed by uncontrol mating practices by smallholder farmers in Cameroon. Within population selection breeding may help to benefit from the within variation. It can also complement for the community based breeding program (CBBP) in Cameroon. CBBP, in which selection within a population is exercised, provides a good framework for the implementation of genomic selection in small holder systems [86]. In this study, the pairwise F_{ST} genetic distance showed that Moroccan goat was closest to Ethiopian goat (S6 Table). This might be because the goats descended from the same origin at the same time, but followed different directions to arrive in the Horn of Africa (Ethiopia) and Morocco. The other possible reason could be connected to the east African Pastoral Neolithic dynamics in which the environmental change and tsetse challenge occurred in the Sahara and north Africa region caused to spread the livestock to east Africa before 2000 BC [87]. However, further investigation is required before firm conclusions can be drawn. Conversely, very high differentiation ($F_{ST} = 0.176$) was observed between Barki and Moroccan goats. This finding is strengthened by the absence of any signature of shared maternal haplotypes between these two populations. In line with this, the MJ network generated with modern maternal DNA showed that the Moroccan lineages were not derived from Egyptian lineages, as would otherwise be expected assuming a terrestrial route for dispersal of the species throughout northern Africa, rather via the Mediterranean routes [88]. Former large-scale mitochondrial analyses [22, 89] have shown that the gene flow towards Morocco did not follow the terrestrial routes. Instead, mtDNA analysis has indicated that the gene flow towards Morocco was via the Mediterranean Sea route, rather than the terrestrial route from Egypt [30].

In the present study, the Neighbor-Net network (Fig 6), the NJ tree (Fig 7) and PCA (Fig 8) differentiated the goat populations based on country of origin. No internal node was detected among Cameroon goats in the Neighbor-Net network, suggesting that the existing populations are intermixed, as supported by the mtDNA and structure results. This indicates that there are no unsampled or lost population(s) from which the existing populations arose [47]. The STRUCTURE analysis also showed that Keffa and Gumez goats (but not other Ethiopian goats) share a considerable proportion of genetic background (10.82% and 6.44%, respectively) with North-west Highland and Djallonke goats of Cameroon at cluster4, $K = 6$ (Fig 9; S7 Table). This observation is in agreement with the shared haplotypes detected (S3 Table). A

recent genome-wide analysis of global goats that clustered east and central African goats together [90] strengthens this observation.

Supporting indications provided by the pairwise F_{ST} and Reynolds' genetic distances (S6 Table), the NJ tree showed that Ethiopian goats were closer to Iranian and Cashmere goats than to Barki goats from Egypt (Fig 7). This is in line with our previous finding of shared haplotypes between Ethiopian and Saudi Arabian goats, which led us to suggest that one possible route of introduction of domestic goats to Ethiopia and the Horn of Africa was via Saudi Arabia, crossing the Red Sea [20]. The STRUCTURE output ($K = 6$) showed that Moroccan and Iranian goats shared 37.83% and 45.43% genetic background, respectively, with Ethiopian goats (Afar, Long-eared Somali, and Nubian) found in hot and arid environments (S7 Table). However, the connection between Cashmere and Ethiopian goats still needs further investigation. Among the other Ethiopian goat populations, Nubian and Afar goats shared 7.51% and 6.08% genetic background with Cashmere goats at cluster3, $K = 6$. This observation support the results obtained with NJ phylogenetic tree and Neighbor-Net network (Figs 6 and 7).

Among the goat populations analyzed, Barki goat (Egypt) and Cashmere goat (China) demonstrated the highest proportion of pure genetic background. The latter has undergone long-term artificial selection for production of Cashmere fiber [91] and could therefore be more genetically homogeneous. Similarly, Barki goat could be naturally selected for adaptation to the extreme arid environment in the western desert in Egypt [92]. In fact, selection signatures that harbor genes associated with adaptation to desert stress have been identified in Barki goat [8].

Approximate Bayesian Clustering (ABC) simulation. The posterior distribution analysis of ABC in the current study indicated that the second scenario in both data sets (mtDNA and autosomal SNP markers) best explains the goat population dynamics towards Cameroon. This indicates that the second route of dispersion of goats in Cameroon and west Africa could be from north Africa in later times (time of most common ancestor (TMCA) ~1518 YA; t_1 ; Table 5). Worth noting is that TMCA was calculated considering at least three years generation interval of goat [93–94]. This goes in line with the phylogenetic network (Fig 6) and admixture outputs that demonstrated 43% common genetic background of Moroccan goats with Cameroon goat populations at cluster 2 and 4 (Fig 9; S7 Table). A recent genome-wide analysis also showed extensive gene flow ($N_m = 25$) amongst the goat populations in Cameroon, Morocco and Ethiopia [90]. In same posterior distribution analysis, the median values of divergence time indicated that Cameroon goats were isolated from their east African cohorts after 1940 generations (5% quantile (q050) = 397 generations–95% quantile (q950) = 5160 generations), which is equivalent to 5820 YA (t_2 ; Table 5). This period earlier than the period of Bantu speaking people movement which was believed happened between 3000–5000 YA [75–78] but later than the arrival time (5000 BC) of goats in north Africa from center of domestication [18]. However, the gene pool arrived to Cameroon and west Africa region from eastward during earlier times could be influenced by tsetse challenge or could be very small. This is supported by low proportion of genetic background (6.4–10.8%) Ethiopian goats shared with Cameroon goats at cluster4 (Fig 9; S7 Table).

In conclusion, this study provided insights about the population history and structure of Cameroon goats. The maternal DNA information revealed only haplogroup A detected in Cameroon. Population differentiation and admixture analyses showed that Cameroon goats appeared to have very low genetic differentiations and have two major genetic backgrounds, with different proportions, but that all three populations analyzed had been intermixed. The goats in Cameroon could have been dispersed from north and east Africa at different times. The haplotype analysis of mtDNA showed the initial dispersion of goats to Cameroon and central Africa from north-east Africa following the Nile Delta as supported by archaeological,

social anthropology and modern human molecular (DNA) evidences. Whereas, the approximate Bayesian computation (ABC) indicated that Cameroon goats were separated from Moroccan goats after 506 generations in later times (~1518 years ago). However, including more mtDNA sequence data from north Africa may warrant to arrive firm conclusion. The differentiation of Barki goat from the other 12 goat populations analyzed shows that Barki goat could be representative of populations found in desert environments for the study of drought tolerance. Interestingly, the autosomal genomic DNA indicated a common origin for Moroccan, Ethiopian and Iranian goats, but this requires further study based on ancient and modern DNA.

Supporting information

S1 Fig. Values of cross validation error plotted against K as generated with STRUCTURE.
(TIFF)

S1 Table. GPS coordinates of Cameroon goat samples included in the study.
(XLSX)

S2 Table. Reference sequences employed for haplogroup analysis.
(DOCX)

S3 Table. Haplotype summary of the goat populations of Cameroon and 29 countries: based on the HVI region of the d -loop.
(XLS)

S4 Table. Distribution of minor allele frequency (MAF) generated from 43421 autosomal SNPs.
(DOCX)

S5 Table. Analysis of molecular variance (AMOVA) for Cameroon goats only using 43421 autosomal SNPs.
(DOCX)

S6 Table. Pairwise genetic distances (F_{ST}) (below diagonal) and Reynolds' distances (above diagonal) among the goat populations studied.
(DOCX)

S7 Table. Proportion of the different genetic backgrounds observed in the study populations as revealed by Admixture analysis for $K = 6$.
(DOCX)

S8 Table. Logistic regression analysis of posterior probabilities (confidence intervals) for the scenarios modelled in DIYABC based on: a) mtDNA simulated for 1,000,000 data set; b) Autosomal markers simulated for 100,000 data set.
(DOCX)

Acknowledgments

We extend special thanks to flock owners and to the district agriculture and rural development offices in Cameroon for support during sampling. We are also grateful to Joram Mwacharo (ICARDA, Addis Ababa Ethiopia) for reviewing the manuscript and providing critical comments.

Author Contributions

Conceptualization: Getinet Mekuriaw Tarekegn, Patrick Wouobeng, Kouam Simo Jaures, Raphael Mrode, Okeyo Ally Mwai, Tadelles Dessie, Kassahun Tesfaye, Josephine Birungi, Appolinaire Djikeng, Félix Meutchieye.

Data curation: Getinet Mekuriaw Tarekegn, Patrick Wouobeng, Kouam Simo Jaures, Raphael Mrode, Zewdu Edea, Bin Liu, Wenguang Zhang, Okeyo Ally Mwai, Tadelles Dessie, Kassahun Tesfaye, Collins Mutai, Sarah Osama, Josephine Birungi, Appolinaire Djikeng, Félix Meutchieye.

Formal analysis: Getinet Mekuriaw Tarekegn.

Funding acquisition: Josephine Birungi.

Investigation: Getinet Mekuriaw Tarekegn.

Methodology: Getinet Mekuriaw Tarekegn, Raphael Mrode, Zewdu Edea, Bin Liu, Wenguang Zhang, Okeyo Ally Mwai, Tadelles Dessie, Kassahun Tesfaye, Erling Strandberg, Britt Berglund, Collins Mutai, Sarah Osama, Asaminew Tassew Wolde, Josephine Birungi, Appolinaire Djikeng, Félix Meutchieye.

Resources: Bin Liu, Wenguang Zhang, Erling Strandberg, Britt Berglund, Asaminew Tassew Wolde, Josephine Birungi.

Supervision: Raphael Mrode, Okeyo Ally Mwai, Tadelles Dessie, Kassahun Tesfaye, Josephine Birungi, Appolinaire Djikeng, Félix Meutchieye.

Writing – original draft: Getinet Mekuriaw Tarekegn.

Writing – review & editing: Getinet Mekuriaw Tarekegn, Patrick Wouobeng, Kouam Simo Jaures, Raphael Mrode, Zewdu Edea, Bin Liu, Wenguang Zhang, Okeyo Ally Mwai, Tadelles Dessie, Kassahun Tesfaye, Erling Strandberg, Britt Berglund, Collins Mutai, Sarah Osama, Asaminew Tassew Wolde, Josephine Birungi, Appolinaire Djikeng, Félix Meutchieye.

References

1. MINEPIA. Rapport Annuel d'Activités 2014 du Projet d'Appui au Développement des Petits ruminants (PADPR). Yaoundé, Cameroun, 2014.
2. Vougat RBN, ChoutO S, Foyet HS, Garabed R, Ziebe R, Zoli AP. Beef consumption and consumer's knowledge on meat quality in Maroua in the Far North of Cameroon; 2016; 10(8) pp. 122–131.
3. FAO (Food and Agriculture organization). FAO Statistical Pocketbook; 2015 <http://www.fao.org/3/a-i4691e.pdf>
4. Peacock CP. Improving Goat Production in the Tropics. A manual for development workers. FARM-Africa/Oxfam, Oxford; 1996.
5. Okpeku M, Yakubu A, Peters SO, Ozoje MO, Ikeobi CON, Adebambo OA, Imumorin IG. Application of multivariate principal component analysis to morphological traits of goats in southern Nigeria. *Acta Agric Slov* 2011; 98: 101–109.
6. Porter V and Mason IL, 2002. *Mason's world dictionary of livestock breeds, types and varieties*. New York: C.A.B International.
7. Chiejina SN, Behnke JM, Fakae BB. Haemonchotolerance in West African Dwarf goats: contribution to sustainable, anthelmintics-free helminth control in traditionally managed Nigerian dwarf goats. *Parasite* 2015; 22 (7).
8. Kim ES, Elbeltagy AR, Aboul-Naga AM, Rischkowsky B, Sayre B, Mwacharo JM et al. Multiple genomic signatures of selection in goats and sheep indigenous to a hot arid environment. *Heredity* 2015; 116(3): 255–264. <https://doi.org/10.1038/hdy.2015.94> PMID: 26555032
9. Pollott G, Wilson RT. Sheep and goats for diverse products and profits. FAO Diversification Booklet N° 9. FAO 2009; 42p.

10. Luna-González A, Hernández-Arteaga S, Sánchez-Garza M, López-Revilla R, Medina-Esparza L, Cruz-Vázquez C. Microsatellite loci and paternity analysis in Nubia and Boer goats. *Arch Med Vet* 2012; 44, 123–127.
11. Huson HJ, Sonstegard TS, Silverstein J, Woodward-Greene MJ, Masiga CW, Muchadeyi FC, et al. Genetic and Phenotypic Characterization of African Goat Populations to Prioritize Conservation and Production Efforts for Small-holder Farmers in Sub-Saharan Africa. *Proceedings, 10th World Congress of Genetics Applied to Livestock Production*; 2014.
12. MacHugh DE, Bradley DG. Livestock genetic origins: Goats buck the trend. *PNAS* 2001; 98:10: 5382–5384.
13. Alemu Y, Merkel RC. *Ethiopian Sheep and Goat Productivity Improvement Program*. Addis Ababa, Ethiopia; 2008; pp348.
14. Zeder MA, Hesse B. The initial domestication of goats (*Capra hircus*) in the Zagros mountains 10,000 years ago. *Science* 2000; 287: 2254–2257. PMID: [10731145](https://pubmed.ncbi.nlm.nih.gov/10731145/)
15. Peters J, von den Driesch A, Helmer D. *The First Steps of Animal Domestication*. *New Archaeological Approaches* Vigne JDPJ, Helmer D, eds. Oxford, UK: Oxbow Books; 2005.
16. Vigne JD. The origins of animal domestication and husbandry: a major change in the history of humanity and the biosphere. *C R Biol* 2011; 334: 171–181. <https://doi.org/10.1016/j.crvi.2010.12.009> PMID: [21377611](https://pubmed.ncbi.nlm.nih.gov/21377611/)
17. Hughes S, Fernández H, Cucchi T, Duffraisse M, Casabianca F, et al. A Dig into the Past Mitochondrial Diversity of Corsican Goats Reveals the Influence of Secular Herding Practices. *PLoS ONE* 2012; 7(1): e30272. <https://doi.org/10.1371/journal.pone.0030272> PMID: [22299033](https://pubmed.ncbi.nlm.nih.gov/22299033/)
18. Hassan FA. Climate and cattle in North Africa: a first approximation. In: Blench RM, MacDonald KC, editors. *The origins and development of African livestock: archaeology, genetics, linguistics and ethnography*. London: UCL Press 2000; Pp 61–86.
19. Gifford-Gonzalez D, Hanotte O. Domesticating Animals in Africa: Implications of Genetic and Archaeological Findings. *J World Prehist* 2011; 24:1–23. <https://doi.org/10.1007/s10963-010-9042-2>
20. Tarekegn GM, Tesfaye K, Mwai OA, Djikeng A, Dessie T, et al. Mitochondrial DNA variation reveals maternal origins and demographic dynamics of Ethiopian indigenous goats. *Ecol Evol* 2018; 8(3):1–11. <https://doi.org/10.1002/ece3.3710>.
21. Luikart G, Gielly L, Excoffier L, Vigne JD, Bouvet J, Taberlet P. Multiple maternal origins and weak phylogeographic structure in domestic goats. *Proceedings of the National Academy of Science USA*, 2001; 98: 5927–5932.
22. Naderi S, Rezaei HR, Taberlet P, Zundel S, Rafat SA, Naghash HR, et al. Large-scale mitochondrial DNA analysis of the domestic goat reveals six maternal lineages with high haplotype diversity. *PLoS ONE* 2007; 10:e1012.
23. Kibegwa FM, Githui KE, Jung'a JO, Badamana MS, Nyamu MN. Mitochondrial DNA variation of indigenous goats in Narok and Isiolo counties of Kenya. *J. Anim. Breed. Genet* 2015; 133(3):238–47. <https://doi.org/10.1111/jbg.12182> PMID: [26459231](https://pubmed.ncbi.nlm.nih.gov/26459231/)
24. Al-Araimi NA, Al-Atiyat RM, Gaafar OM, Vasconcelos R, Luzuriaga-Neira A, Eisa MO, et al. Maternal genetic diversity and phylogeography of native Arabian goats. *Livestock Science* 2017a; 206: 88–94.
25. Al-Araimi NA, Gaafar OM, Costa V, Neira AL, Al-Atiyat RM, Beja-Pereira A. Genetic origin of goat populations in Oman revealed by mitochondrial DNA analysis. *PLoS ONE* 2017b; 12(12): e0190235. <https://doi.org/10.1371/journal.pone.0190235> PMID: [29281717](https://pubmed.ncbi.nlm.nih.gov/29281717/)
26. Tesfaye AT. Genetic characterization of indigenous goat populations of Ethiopia using microsatellite DNA markers. A PhD thesis submitted to the national dairy research institute, Deemed University. Karnal-Haryana, India, 2004.
27. Chenyambuga SW, Hanotte O, Hirbo J, Watts PC, Kemp SJ, Kifaro GC. Genetic Characterization of Indigenous Goats of Sub-saharan Africa Using Microsatellite DNA Markers. *Asian Australasian Journal of Animal Sciences* 2004; 17(4). <https://doi.org/10.5713/ajas.2004.445>
28. Guangul SA. Design of community based breeding programs for two indigenous goat breeds of Ethiopia. Doctoral Thesis: University of natural resources and applied life sciences, department of sustainable agricultural systems division of livestock sciences. Vienna, Austria 2014.
29. Tarekegn GM, . Molecular characterization of Ethiopian indigenous goat populations: genetic diversity, demographic dynamics and kisspeptin gene polymorphism. PhD dissertation. Addis Ababa University, Addis Ababa Ethiopia; June 2016.
30. Benjelloun B, Pompanon F, Ben Bati M, Chentouf M, Ibelbachyr M, El Amiri B, et al. Mitochondrial DNA polymorphism in Moroccan goats. *Small Ruminant Research* 2011; 98: 201–205
31. Rahmatalla SA, Arends D, Reissmann M, Ahmed AS, Wimmers K, Reyer H, Brockmann GA. Whole genome population genetics analysis of Sudanese goats identifies regions harboring genes associated

- with major traits. *BMC Genetics* 2017; 18:92. <https://doi.org/10.1186/s12863-017-0553-z> PMID: 29058610
32. Meutchieye F, Ema-Ngono P J, Agaba M, Djikeng A, Manjeli Y. Genetic diversity of Cameroon indigenous goat populations using microsatellites. *Livestock Research for Rural Development*. 2014; 26: *Article #128*. Retrieved May 13, 2017, from <http://www.lrrd.org/lrrd26/7/meut26128.htm>
 33. Singh N, Choudhury DR, Singh AK, Kumar S, Srinivasan K, et al. Comparison of SSR and SNP Markers in Estimation of Genetic Diversity and Population Structure of Indian Rice Varieties. *PLoS ONE* 2013; 8 (12): e84136. <https://doi.org/10.1371/journal.pone.0084136> PMID: 24367635
 34. Tosser-Klopp G, Bardou P, Bouchez O, Cabau C, Crooijmans R, et al. Design and Characterization of a 52K SNP Chip for Goats. *PLoS ONE* 2016; 11(3): e0152632. <https://doi.org/10.1371/journal.pone.0152632> PMID: 27011020
 35. Epstein H. *The Origin of Domestic Animals of Africa*. Vol. II. Africana Publishing Corporation, New York 1971; 957 pp.
 36. Tamura K, Stecher G, Peterson D, Filipowski A, Kumar S. MEGA6: Molecular Evolutionary Genetics Analysis Version 6.0. *Molecular Biology and Evolution* 2013; 30, p. 2725–2729. <https://doi.org/10.1093/molbev/mst197> PMID: 24132122
 37. Thompson JD, Higgins DG, Gibson TJ. CLUSTAL W: improving the sensitivity of progressive multiple sequence alignment through sequence weighting, position-specific gap penalties and weight matrix choice. *Nucleic Acids Res* 1994; 22, 4673–4680. PMID: 7984417
 38. Librado P, Rozas J. DnaSP v5: a software for comprehensive analysis of DNA polymorphism data. *Bioinformatics applications note* 2009; 25 (11): 1451–1452.
 39. Excoffier L, Lischer HEL. Arlequin suite ver 3.5: A new series of programs to perform population genetics analyses under Linux and Windows. *Molecular Ecology Resources* 2010; 10: 564–567. <https://doi.org/10.1111/j.1755-0998.2010.02847.x> PMID: 21565059
 40. Bandelt HJ, Forster P, Röhl A. Median-joining networks for inferring intraspecific phylogenies. *Mol Bio Evo* 1999; 16(1):37–48.
 41. Rogers AR, Harpending H. Population growth makes waves in the distribution of pairwise genetic differences. *Mol Biol Evol* 1992; 9:552–569. <https://doi.org/10.1093/oxfordjournals.molbev.a040727> PMID: 1316531
 42. Harpending HC. Signature of ancient population growth in a low-resolution mitochondrial DNA mismatch distribution. *Hum Biol* 1994; 66:591–600. PMID: 8088750
 43. Fu YX. Statistical tests of neutrality of mutations against population growth, hitchhiking and background selection. *Genetics* 1997; 147:915–925. PMID: 9335623
 44. Tajima F. Statistical method for testing the neutral mutation hypothesis by DNA polymorphism. *Genetics* 1989; 123 (3): 585–95. PMID: 2513255
 45. Reynolds J, Weir BS, Cockerham CC. Estimation of the coancestry coefficient: basis for a short-term genetic distance. *Genetics* 1983; 105: 767–779. PMID: 17246175
 46. Weir BS, Cockerham CC. Estimating F-statistics for the analysis of population structure. *Evolution* 1984; 38:1358–70. <https://doi.org/10.1111/j.1558-5646.1984.tb05657.x> PMID: 28563791
 47. Huson DH, Bryant D. Application of Phylogenetic Networks in Evolutionary Studies. *Mol. Biol Evol* 2006; 23(2):254–267. <https://doi.org/10.1093/molbev/msj030> PMID: 16221896
 48. Bradbury PJ, Zhang Z, Kroon DE, Casstevens TM, Ramdoss Y, Buckler ES. TASSELE: Software for association mapping of complex traits in diverse samples. *Bioinformatics* 2007; 23:2633–2635. <https://doi.org/10.1093/bioinformatics/btm308> PMID: 17586829
 49. DCT (Development Core Team). R: A Language and Environment for Statistical Computing. Vienna, Austria: the R Foundation for Statistical Computing. 2014; ISBN: 3-900051-07-0. Available online at <http://www.R-project.org/>.
 50. Zheng X, Levine D, Shen J, Gogarten SM, Laurie C, Weir BS. A High-performance Computing Toolset for Relatedness and Principal Component Analysis of SNP Data. *Bioinformatics*. 2012; <https://doi.org/10.1093/bioinformatics/bts610>
 51. Pritchard JK, Stephens M, Donnelly P. Inference of population structure using multilocus genotype data. *Genetics* 2000; 155, 945–959. PMID: 10835412
 52. Earl DA. STRUCTURE HARVESTER: a website and program for visualizing STRUCTURE output and implementing the Evanno method. *Conserv. Genet. Resour* 2012; 4: 359–361. <https://doi.org/10.1007/s12686-011-9548-7>
 53. Evanno G, Regnaut S, Goudet J. Detecting the number of clusters of individuals using the software STRUCTURE: a simulation study. *Mol Ecol* 2005; 14: 2611–2620. <https://doi.org/10.1111/j.1365-294X.2005.02553.x> PMID: 15969739

54. Beaumont MA, Zhang W, Balding DJ. Approximate Bayesian Computation in Population Genetics. *Genetics* 2002; 162: 2025–2035. PMID: [12524368](#).
55. Cornuet JM, Pudlo P, Veyssier J, Dehne-Garcia A, Gautier M, Leblois R, Marin JM, Estoup A. DIYABC v2.0: a software to make Approximate Bayesian Computation 35 inferences about population history using Single Nucleotide Polymorphism, DNA sequence and 36 microsatellite data 2014 Vol. 30(8) 1187–1189.
56. Cornuet JM, Santos F, Beaumont MA, Robert CP, Marin JM, Balding DJ, et al. Inferring population history with DIYABC: a user-friendly approach to approximate Bayesian computation. *Bioinformatics* 2008; 24: 2713–2719. <https://doi.org/10.1093/bioinformatics/btn514> PMID: [18842597](#)
57. Cornuet JM, Ravugne V, Estoup A. inference on population history and model checking using DNA sequence and microsatellite data with the software DIYABC (v1.0). *BMC Bioinformatics* 2010; 11:401. <https://doi.org/10.1186/1471-2105-11-401> PMID: [20667077](#)
58. Awotunde EO, Bemji MN, Olowofeso O, James IJ, Ajayi OO, Adebambo AO. Mitochondrial DNA Sequence Analyses and Phylogenetic Relationships Among Two Nigerian Goat Breeds and the South African Kalahari Red, *Animal Biotechnology* 2015; 26(3): 180–187, <https://doi.org/10.1080/10495398.2014.977907> PMID: [25695640](#)
59. Bwihangane BA, Gitao GC, Bebora LC, Tarekegn MG, Nicholas S, Bacigale S, Svitek N. Mitochondrial DNA variation of indigenous goat populations from Peste-des-petits-ruminants outbreak in South Kivu, Democratic Republic of the Congo. *Livestock Research for Rural Development* 2018; 30(18). Retrieved January 9, 2018, from <http://www.lrrd.org/lrrd30/1/adjj30018.html>
60. Benjelloun B, Alberto FJ, Streeter I, Boyer F, Coissac E, Stucki S, et al. Characterizing neutral genomic diversity and selection signatures in indigenous populations of Moroccan goats. *Front Genet* 2015; 6:107. <https://doi.org/10.3389/fgene.2015.00107> PMID: [25904931](#)
61. Okpeku M, Peters SO, Imumorin IG, Caires KC, Sharma VK, Wheto M, et al. Mitochondrial DNA hyper-variable region 1 diversity in Nigerian goats. *Animal Genetic Resources* 2016; 59: 47–54. <https://doi.org/10.1017/S2078633616000102>
62. Clutton-Brock J. Cattle, sheep, and goats south of the Sahara: An archaeozoological perspective. In ench KC R. M. MacDonald(Eds.), *The origins and development of African livestock: Archaeology, genetics, linguistics and ethnography* 2000; Pp. 30–37. London, UK: UCL Press.
63. Smith AB. Biogeographical considerations of colonization of the lower Tilemsi Valley in the 2nd millennium B. C. *J. Arid Environ* 1979; 2:355–61
64. Smith AB. The origins of the Neolithic in the Sahara. In *From Hunters to Farmers: the causes and consequences of food production in Africa* (eds Clark J. D. and Brandt S. A.). 1984; 84–92. Berkeley: University of California Press.
65. Smith AB. Origins and Spread of Pastoralism in Africa. *Annual Review of Anthropology*, 1992; 21:125–141. <https://www.jstor.org/stable/2155983>
66. Clark JD. The domestication process in sub-Saharan Africa with special reference to Ethiopia. In *Origine de l'Élevage et de la Domestication*, ed. Higgs E. 1976; 56–115. Nice: IXth Congr. IUSPP
67. Brandt SA. New perspectives on the origins of food production in Ethiopia. See Ref. 15a, 1984: 173–90
68. Castrì L, Tofanelli S, Garagnani P, Bini C, Fosella X, Pelotti S, et al. MtDNA variability in two Bantu-speaking populations (Shona and Hutu) from Eastern Africa: Implications for peopling and migration patterns in sub-Saharan Africa. *American Journal of Physical Anthropology* 2009; 140 (2): 302–11. <https://doi.org/10.1002/ajpa.21070> PMID: [19425093](#)
69. Alves I, Coelho M, Gignoux C, Damasceno A, Prista A, Rocha J. Genetic homogeneity across Bantu-speaking groups from Mozambique and Angola challenges early split scenarios between East and West Bantu populations. *Human Biology* 2011; 83 (1): 13–38. <https://doi.org/10.3378/027.083.0102> PMID: [21453002](#)
70. de Filippo C, Barbieri C, Whitten M, Mpoloka SW, Gunnarsdóttir ED, Bostoen K, Nyambe T, Beyer K, Schreiber H, de Knijff P, Luiselli D, Stoneking M, Pakendorf B. Y-chromosomal variation in Sub-Saharan Africa: insights into the history of Niger-Congo groups. *Molecular Biology and Evolution* 2011; 28 (3): 1255–69. <https://doi.org/10.1093/molbev/msq312> PMID: [21109585](#)
71. Johnston HH. A survey of the ethnography of Africa: and the former racial and tribal migrations of that continent. *J. R. Anthropol. Inst.* XLIII, 1913; 391–392.
72. Greenberg JH. Linguistic evidence concerning Bantu origins. *J. Afr. Hist.* 1972; 13: 189–216. (<https://doi.org/10.1017/S0021853700011427>).
73. Huffman TN. Archaeology and the ethnohistory of the African Iron Age. *Annu. Rev. Anthropol* 1982; 11: 133–150. (<https://doi.org/10.1146/annurev.an.11.100182.001025>).
74. Vogel JO. Eastern and south-central African Iron Age. In *Encyclopedia of precolonial Africa* (ed. Vogel JO) 1994: 439–444. Walnut Creek, CA: Alta-Mira Press.

75. Ehret C, Posnansky M. The archaeological and 13. linguistic reconstruction of African history. Berkeley, CA: University of California Press 1982.
76. Phillipson DW. African Archaeology. Cambridge Univ. Press, ed. 2, 1993.
77. Vansina J. New linguistic evidence and the Bantu expansion. *J. Afr Hist* 1995; 36: 173–195. (<https://doi.org/10.1017/S0021853700034101>).
78. Holden CJ. Bantu language trees reflect the spread of farming across sub-Saharan Africa: a maximum-parsimony analysis. *Proc. R. Soc. Lond. B* 2002; 269: 793–799. <https://doi.org/10.1098/rspb.2002.1955> PMID: 11958710
79. Li S, Schlebusch C, Jakobsson M. Genetic variation reveals large-scale population expansion and migration during the expansion of Bantu-speaking peoples. *Proc. R. Soc. B* 2014; 281: 20141448. <https://doi.org/10.1098/rspb.2014.1448> PMID: 25209939
80. Patin E, Lopez M, Grollemund R, Verdu P, Harmant C, Quach H, et al. Dispersals and genetic adaptation of Bantu-speaking populations in Africa and North America. *Science* 2017; 356, 543–546. <https://doi.org/10.1126/science.aal1988> PMID: 28473590
81. Mekuriaw G, Mwacharo J, Tesfaye K, Dessie T, Mwai O, Djikeng A, et al. High Density SNP Chips Array Uncovers Genetic Diversity and Population Structure of 16 Ethiopian and Chinese Goat Populations. Plant and Animal Genomics XXIV meeting: International Goat Genomics Consortium, held in San Diego, USA in January 09–13, 2016. <https://pag.confex.com/pag/xxiv/meetingapp.cgi/Person/39319>.
82. Nicoloso L, Bomba L, Colli L, Negrini R, Milanese M, Mazza R, et al. Genetic diversity of Italian goat breeds assessed with a medium-density SNP CHIP. *Genetics Selection Evolution* 2015; 47:62.
83. Bamshad MJ, Mummidi S, Gonzalez E, Ahuja SS, Dunn DM, Watkins WS, et al. A strong signature of balancing selection in the 5 cis-regulatory region of CCR5. *PNAS* 2002; 99 (16): 10539–10544 <https://doi.org/10.1073/pnas.162046399> PMID: 12149450
84. Charlesworth D. Balancing selection and its effects on sequences in nearby genome regions. *PLoS Genet* 2006; 2(4): e64. <https://doi.org/10.1371/journal.pgen.0020064> PMID: 16683038
85. Visser C, Lashmar SF, Van Marle-Köster E, Poli MA, Allain D. Genetic Diversity and Population Structure in South African, French and Argentinian Angora Goats from Genome-Wide SNP Data. *PLoS ONE* 2016; 11(5): e0154353. <https://doi.org/10.1371/journal.pone.0154353> PMID: 27171175
86. Mrode R, Tarekegn GM, Mwacharo JM, Djikeng A. Invited review: Genomic selection for small ruminants in developed countries: how applicable for the rest of the world? *Animal* 2018; 12(7):1333–1340 <https://doi.org/10.1017/S1751731117003688> PMID: 29343308
87. Bower J. The Pastoral Neolithic of east Africa. *J. World Prehistory* 1991; 5(1).
88. Pereira F, Queirós S, Gusmão L, Nijman IJ, Cuppen E, Lenstra JA, et al. Tracing the History of Goat Pastoralism: New Clues from Mitochondrial and Y Chromosome DNA in North Africa. *Mol. Biol Evol* 2009; 26(12):2765–2773. <https://doi.org/10.1093/molbev/msp200> PMID: 19729424
89. Luikart G, Fernández H, Mashkour M, England PR, Taberlet P. Origins and diffusion of domestic goats inferred from DNA markers example analyses of mtDNA, Y Chromosome, and microsatellites. Documenting documentations: New genetic and archaeological paradigms. University of California press. Berkeley Los Angeles London 2006.
90. Colli L, Milanese M, Talenti A, Bertolini F, Chen M, et al. Genome-wide SNP proling of worldwide goat populations reveals strong partitioning of diversity and highlights post-domestication migration routes. *Genet Sel Evol*; 2018, 50:58 <https://doi.org/10.1186/s12711-018-0422-x> PMID: 30449284
91. Liu R, Sun Y, Zhao G, Wang F, Wu D, et al. Genome-Wide Association Study Identifies Loci and Candidate Genes for Body Composition and Meat Quality Traits in Beijing-You Chickens. *PLoS ONE* 2013; 8 (4): e61172. <https://doi.org/10.1371/journal.pone.0061172> PMID: 23637794
92. Haider AI. Studies of the performance of some breeds of goats and their crosses under desert condition in Egypt. PhD Thesis, Faculty of Agriculture, Alexandria University Egypt 1982.
93. Al-Atiyat RM and Aljumaah RS. Simulated breeding scenarios for improving Hejaz goat performance in subtropics. *Food, Agriculture & Environment* 2013; 11 (2): 440–444.
94. Facó O, Lôbo RNB, Gouveia AMG, de Paiva Guimarães MP, Fonseca JF, Maciel dos Santos TN, Alves da Silva MA and Villela LCV. Breeding plan for commercial dairy goat production systems in southern Brazil. *Small Ruminant Research* 2011; 98: 164–169.